

GAF ARMORSHIELD II RE-ROOF PROPOSAL V.2



Holladay Grace
7917 Red Granite Loop
Suite 100
Colorado Springs, CO 8093
holladaygrace@holladaygrace.com
(719) 596-0799

For: Mary Smith

Proposal Amount \$12,012.35

Description

Project Materials

- GAF Armorshield II Shingle 3BD/SQ
- Top Shield Synthetic Underlayment 10SQ/RL
- GAF Weatherwatch Ice & Water 2SQ/RL
- GAF Prostart Starter 120LF/BD
- GAF Armorshield II Seal-A-Ridge Hip & Ridge 25LF/BD
- 2x4 Drip Edge Painted 90 Degree - Rake
- Lomanco 750 Roof Vent 8"
- 3-1 Pipe Jack 1 1/2" - 3"
- Prebent Step Flashing 4"x4"x8" - Painted
- Counter Flashing 10LF
- Plastic Caps 1 1/4" 2500pc
- Coil Nails 1 1/4"
- Top Shield Elastomeric Sealant 10.1 oz
- Geocel Spray Paint 12 oz
- 5" Adj Roof Flashing
- 5" Dura-Vent Cap
- Roof Decking
- 7/16 OSB

Project Labor

Shingles-Remove and Replace

Up to and including installing Lifetime dimensional shingles including starter, ridge caps, felt, I&W, drip edge, R&R vents, R&R pipe jacks, R&R Valley, R&R step flashing, Electric Masthead and 1 layer tear off, < 6/12 and legal disposal

Double Felt

Chimney Flashing

Install Roof Sheeting- 7/16" OSB

Misc. Items

Permit Fee

Standard Permit Fee

Delivery

Materials rooftop loaded

GAF Systems Plus Warranty

GAF Systems Plus Warranty requires the installation of 3 GAF accessory products

Total \$12,012.35

Customer Signature:

07/21/2022